



Woodstock, Vermont *The Shire Town of Windsor County*

TOWN - VILLAGE MANAGER GOVERNMENT

Town Hall • P.O. Box 488 • Woodstock, Vermont 05091 • 802/457-3456

Town of Woodstock Invitation to Bid Resetting Curbing and Sidewalk Work 2019

Project:

The Town of Woodstock is soliciting proposals from qualified firms for a project within the Village of Woodstock to reset curbing and replace sidewalks on South Street, Elm Street, Pleasant Street, and Central Street.

Mandatory Site Visit

There will be a mandatory site visit on **June 10th, 2019 at 10:00am** at the Woodstock Town Hall, 31 The Green, 2nd Floor Conference Room. Meet at Town Hall and then we will travel to the site to review the project.

Scope of Work:

Resetting Curbing:

- South Street:
 - Granite Curb +/- 1295 ft
 - Paved Curb +/- 885 ft
- Elm Street:
 - Granite Curb +/- 4101 ft
 - Paved Curb +/- 376 ft
- Pleasant Street
 - Granite Curb +/- 207 ft
 - Paved Curb +/- 333 ft
- Central Street:
 - To the dummy. This will be explained at the pre-bid meeting.

Resetting Curbing to include:

- Saw and cut the pavement where necessary.
- Remove and dispose of pavement.
- Remove and save granite curbing.
- Excavate trench to grade. (Town will provide grades)
- Reset the curbing; level and square
- Pour concrete (3,000 psi) in front and behind curbing.
- Mortar joints after concrete is poured (and set for a minimum of 24hrs.)
- Back fill with native soil unless otherwise approved.
- Repave to grade and cut line(s) of pavement.
- Remove any residual mortar from curbing. (clean)
- Grass restoration (where applicable) seed, fertilizer, and mulch hay.
- Clean the street.
- Protect pedestrian and vehicular traffic from jobsite dangers.



Sidewalk Work:

- South Street:
 - Paved Sidewalk +/- 2788 ft
- Elm Street:
 - Paved Sidewalk +/- 1894 ft
 - Concrete Sidewalk +/- 400 ft
- Pleasant Street
 - Paved Sidewalk +/- 1008ft
- Central Street:
 - This will be explained at the pre-bid meeting.

Sidewalk Work to Include:

- Cut pavement/concrete where necessary.
- Remove old sidewalk.
- Regrade and compact.
- Replace sidewalk in kind.
- Clean up the street and sidewalk.
- Protect pedestrian and vehicular traffic from jobsite dangers.
- Sidewalk pavement to be a minimum of 2" thick with 1/2" aggregate base (1" thick) and 3/8" topcoat, rolled at each level.

Proposals:

- Should include the following:
 - Total of all work for all 4 streets.
 - Total of all work for each street separately.
 - Total for all curbing work for all 4 streets.
 - Total for all sidewalk work for all 4 streets.
 - Total for all curbing work for each street.
 - Total for all sidewalk work for each street.

Bids:

Bids are due on **Thursday June 20th, 2019** at Town Offices at 2:00PM.

Bids will be opened publicly in the Municipal Manager's Office at the Woodstock Town Hall located at 31 The Green.

Please submit bids by mail to:

Philip Swanson, Municipal Manager
Woodstock Town Hall
P.O. Box 488
Woodstock, VT 05091

****Mark on the outside of the envelope-"Curbing and Sidewalk work".**

Questions

Please contact Ken Vandenburg if questions: (802) 457-2233; dpw@townofwoodstock.org

Award will be based on price and other considerations.

All Bidders must include proof of Worker's Compensation at time of award.

Women and minority owned businesses are encouraged to submit a proposal.

The Town of Woodstock reserves the right to reject any and all bids received.